

BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Name of the Work: Improvements to Roads and Drains at Canara Bank Layout Main Road and Cross Roads and Surrounding areas in Ward No. 09 (Vidyaranyapura).

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	1013.63	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	243.88	Rupees Two Hundred Forty Three and Eighty Eight Paise Only
2	1073.25	Removing and refixing stone slabs of drains and pointing in CM (1:3) etc complete as per specifications and directions of engineer in charge of the work	Sqm	111.30	Rupees One Hundred Eleven and Thirty Paise Only
3	110.54	Providing granite slabs of selected quality roughly dressed havinf a size of 7.5 cms thick and fixed in cement mortar (1:6) including fixing curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	742.00	Rupees Seven Hundred Forty Two Only
4	159.00	Providing and laying Plain cement concrete of mix 1:3:6 with with OPC cement @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @ 0.56cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days complete as per specifications and directions of engineer in charge of the work	Cum	5421.90	Rupees Five Thousand Four Hundred Twenty One and Ninety Paise Only
5	2120.00	Providing and constructing load bearing wall with solid concrete blocks of size 400x150x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 4.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	979.44	Rupees Nine Hundred Seventy Nine and Forty Four Paise Only
6	157.30	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggretes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills , ncluding cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5599.98	Rupees Five Thousand Five Hundred Ninety Nine and Ninety Eight Paise Only

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
7	1344.60	Providing precast slab of 100 mm thick including cost of all materials, labour, curing, transportation, loading unloading, etc., complete as per the direction of engineer in charge- ~~Data rate.~~	Sqm	2337.00	Rupees Two Thousand Three Hundred Thirty Seven Only

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

Note:

- Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)
- Unit rates and prices shall be quoted by the Tender in Indian rupees.
- Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a))
- Where there is a discrepancy between the unit rate and the line item total resulting from multiplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

ಕಂಡಿಕೆ () ರಲ್ಲಿ ವಿವರಿಸಿರುವಂತೆ ಅಂಶಗಳ ಬಗ್ಗೆ
ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು() ರವರು
ದೃಢೀಕರಿಸಿಕೊಳ್ಳುವ ಹಕ್ಕನ್ನು ಒಳವಡಿಸಿ ಡಿ.ಟಿ.ಎಸ್
ಅನುಮೋದಿಸಿದರು.
ಕರಡು ಬೆಂಚ್ ಮೇಲ್ಮೈನು ಇವುಗಳ ಮೇಲೆ ಮಾಡದಂತೆ
ತಿದ್ದುಪಡಿ ಇಲ್ಲದೆ ಅನುಮೋದಿಸಿ ನೀಡಲಾಗಿದೆ.
ತಿದ್ದುಪಡಿಸಿದ ಒಟ್ಟು ಸಂಖ್ಯೆ : ①
ರದ್ದುಗೊಳಿಸಿರುವ ಒಟ್ಟು ಐಟಂಗಳ ಸಂಖ್ಯೆ : —
15/11/2020
ಅಧೀಕ್ಷಕ ಅಭಿಯಂತರರು (ಅನುಮೋದನೆ)